



THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELATED DRAWINGS. ALL DIMENSIONS MUST BE CHECKED AND VERIFIED ON SITE BEFORE COMMENCING ANY WORK OR PRODUCING SHOP DRAWINGS. THE ORIGINATOR SHOULD BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCY. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF ROGER PARRY & PARTNERS.

**Planting Specification**

**Topsoil** – all planting is to take place in the existing agricultural soils on site.

**Planting and Plants** – all planting and plants shall be healthy in appearance and comply with the requirements of all current/relevant British Standards including BS3936 and BS4428. All planting to be carried out within the recognised planting season of November to March. All plants to be British grown stock and fully hardened off. All native species to be of local origin.

**Root Dip** – proprietary root dip to be applied to all bare rooted stock at the time of lifting at the nursery and prior to planting.

**Planting Management**

- Any plants affected by frost heave shall be replaced.
- Protective fencing and stakes with ties and guards are to be inspected and maintained on a regular basis over a number of visits to site over the first five years following planting.
- Any damage is to be repaired or replaced as necessary.
- Further standard maintenance shall include watering, pest control and disease control.
- Regular visits shall be made to the hedgerows to ensure the newly planted stock is in weed free condition.

**Weed Control**

Hand weeding will be undertaken to remove weeds surrounding the new planting. An approved herbicide will be used in Years 1 to 3 to ensure healthy growth and weed free areas.

**Hedgerow Planting**

Hedging plants are to be planted in tranches wide enough to allow the plants full root spread. Plants to be set out in double staggered rows using a total of 5 plants per linear metre. Proprietary guards shall be applied in accordance with the recommendations of the manufacturer.

**Timetable**

The planting shall be completed within 12 months of completion of the development approved.

**Native Hedgerow Mix**

Percentage	Species	Size	Spacing
30%	Acer campestre/Field Maple	400-600mm	5 per linear metre
20%	Corylus avellana/Hazel	400-600mm	5 per linear metre
35%	Crataegus monogyna/Hawthorn	400-600mm	5 per linear metre
10%	Ilex aquifolium/Holly	400-600mm	5 per linear metre
5%	Viburnum opulus/Guelder Rose	400-600mm	5 per linear metre

Rev	Description	Date	Dr by	App by
Original				



Residential - Agricultural - Commercial	
Job	Poultry unit at Drefor
Title	Landscaping Plan
Location	Drefor Kerry Newtown Powys SY16 4PQ
Client	M & A Powell
Scales	1:1250 @ A3
Drawing No.	RJC-MZ335-05
Drawn by	AZ
Date	23/01/2020

HOGSTOW HALL, MINSTERLEY  
SHREWSBURY, SHROPSHIRE, SY5 0HZ  
Tel: 01743 791336 Fax: 01743 792770  
email: mail@rogerparry.net  
Web address: www.rogerparry.net