
Root Protection plan for the hedgerows and mature trees

Erection of an 8,000 Bird Extension to the
existing Free Range Poultry Unit at
Gwynfaes
Rhandirmwyn
Llandovery
Carmarthenshire
SA20 0NG

Prepared for AS, S & ME Reah



land & property
professionals

Roger Parry & Partners LLP
www.rogerparry.net
gail@rogerparry.net
Tel: 01691 655334

1. INTRODUCTION

The purpose of this report is to detail the Arboriculture Method Statement and Tree Protection Plan as a result of the proposals at Gwynfaes, Rhandirmwyn, in accordance with BS 5837.

The report seeks to ensure the safe and healthy retention of all trees surrounding the development proposed.

2. PROPOSAL

- a) The Root protection area for the surrounding trees and hedgerows will be established by the project site manager, based on the width of the established trees, and the height of the hedgerow. The Root protection area shall be designed to protect at least a functional minimum of tree root mass to ensure that the trees all survive the construction process.
- b) It is the responsibility of everyone engaged in the construction process to respect the tree protection measures and observe the necessary precautions within and adjacent to them.
- c) Within the tree protection fencing there shall be;
 - no mechanical excavation;
 - no excavation by any other means;
 - no hand digging;
 - no ground level changes;
 - no storage of materials;
 - no storage or handling of any chemicals.
- d) No vehicular access within the root protection areas.
- e) No development within 5metres of an existing, established hedgerow.