

THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELATED DRAWINGS. ALL DIMENSIONS MUST BE CHECKED AND VERIFIED ON SITE BEFORE COMMENCING ANY WORK OR PRODUCING SHOP DRAWINGS. THE ORIGINATOR SHOULD BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCY. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY ROGER PARRY & PARTNERS.

Notes:


The underground storage tank for dirty water will be constructed to meet the SSAFO Regulations (Wales) 2010 Standards.

Clean water from roof and clean surfaces to open and stone filled infiltration trenches and a piped system each side of building. This is then discharged into soakaway.

At the wash down stage the clean water system around the yard will be switched to the underground dirty water tank (shown blue on the plan).

The clean and foul water drainage systems will be kept separate in order to ensure no pollution incident occurs to the environment.

All dirty water from wash down will be collected in an underground sealed tank. This will be then tankered out as necessary and applied to the land in accordance with the farm manure management plan (shown red on the plan).



Rev	Description	Date	Dr by	App by
Original				



Residential - Agricultural - Commercial	
Job	Proposed Broiler Unit
Title	Drainage Plan
Location	Land near Llwyngwilym Rhayader Powys LD6 5NS
Client	J Powell
Scales	1:500 @ A1
Drawing No.	GEL/JP/BU/002
Drawn by	GEL-MZ246-02
Date	30/07/2018

HOGSTOW HALL, MINSTERLEY
SHREWSBURY, SHROPSHIRE, SY5 0HZ
Tel: 01743 791336 Fax: 01743 792770
email: mail@rogerparry.net
Web address: www.rogerparry.net