Ecological Enhancement Key

- S — Integral eco-habitat for Swifts. 4No. within fabric
- H — Integral Sparrow house. 2No. within fabric
- W — 1ZA Roundhouse Wren box. 2No. within new tree planting
- B — Schwegler 1b bird box. 2No. within new tree planting
- B — Integral enclosed Bat box type 'C'. 4No. within fabric
- H — Hedgehog friendly fencing to allow for free movement between internal and external site boundaries

BENCH SEATING
Treated Timber Slats over Cast Concrete

SITE FINISHES

EXTERNAL FINISH TYPE 01
600x600mm / 900x600mm standard commercial concrete paving slabs

EXTERNAL FINISH TYPE 02
Permeable Tarmac - Road Surface

EXTERNAL FINISH TYPE 03
Marshalls Tegula permeable block paving - Charcoal

EXTERNAL FINISH TYPE 04
Marshalls Tegula permeable block paving - Traditional

EXTERNAL FINISH TYPE 05
Self binding Gravel (to match paving)

EXTERNAL FINISH TYPE 06
Resin Bound Gravel (to match paving)

EDGE TYPE 01
Marshall's Textured Conservation Kerb - Silver Grey

EDGE TYPE 02
Conveyance Channel

PROPOSED AMENITY GRASS
300mm soil depth formed of 150mm topsoil over 150mm subsoil

EXISTING HEDGEROW / VEGETATION RETAINED
Existing mixed hedgerow to be retained and / or relocated - refer to Tree protection and Removal Plan for detail

PROPOSED NEW AND INFILL HEDGEROW
Species rich native mixed hedgerow - bare root stock 90-120cm tall planted as double staggered rows at 7 per linear metre. Species to be identified from existing.

PROPOSED WILDFLOWER AND GRASS SEED
Emorsgate seed mix; general purpose meadow mixture
300mm soil depth formed of 150mm topsoil over 150mm subsoil

PROPOSED ORNAMENTAL PLANTING
600mm soil depth formed of 300mm topsoil over 300mm subsoil
- Choisya 'Aztec Pearl'
- Choisya Ternata
- Fatsia Japonica
- Skimmia Japonica
- Miscanthus Sinensis 'Morning Light'
- Miscanthus Sinensis 'Malepartus'
- Viburnum Davidii
- Osmanthus Heterophyllus
- Fatsia Japonica
- Myrtus Communis
- Hebe 'Midsummer Beauty'
- Philadelphus Microphyllus
- Phormium 'Bronze Baby'
- Phormium 'Yellow Wave'
- Hedera Helix 'Glacier'
- Hakonechloa Macra 'Albaaurea'
- Vinca Major
- Vinca Minor 'Gertrude Jekyll'

ATTENUATION RAIN GARDEN
800mm depth formed of 200mm Freeboard, 300mm topsoil(50%sand 30% topsoil 20% compost) over 300mm subsoil. To contain a mix of
- Crocosmia
- Vinca Minor
- Carex Pendula
- Iris Sibirica

TREE
900mm soil depth formed of 300mm topsoil over 600mm subsoil.
- Common Hawthorn (Crataegus monogyna)
- Rowan (Sorbus aucuparia)
- Double Crimson Flowering Hawthorn (Crataegus laevigata 'Paul's Scarlet')

BOUNDARY TYPE 01 -
1.8m Timber Hit & Miss Fence

BOUNDARY TYPE 02 -
215mm facing brickwork wall

PRELIMINARY

A 11/08/2022 Red line boundary amended.

Hiraeth.

2212 P 210

Rev. A

Mid Wales Property
Land At Wallers, Trewern

PROPOSED SITE LANDSCAPE MASTERPLAN

Scale 1:250 @ A1 , 1:500 @ A3 Date 07/22

02920351645 | office@hiraetharchitecture.co.uk
The Maltings | East Tyndall St | Cardiff | CF24 5EA

do not scale from this drawing | all dimensions to be verified on site | notify architect of all discrepancies | copyright Hiraeth architecture